ENGINEERING DEPARTMENT.

BANGALORE DIVISION.

Notice dated 3rd November 1930.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 25th November 1930, for extending the Chief Commandant's Office at Hebbal. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1931.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees two hundred (200) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for extending Chief Cammandant's Office at Hebbal," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract.

No.	Items of work	Unit	Rate	Quantity
1	Dismantling walls and removing debris ...	C.ft.	Rs. a. p.	326
2	Earthwork excavations for foundation and filling in basement with water and consolidation.	C.yd.		58
3	Burnt stone jelly concrete	,,		498
4	Burnt brick in clay	,,		3,151
5	Burnt stone in clay	,,		1,453
6	Burnt brick in mortar	,,		496
7	Arch works do in mortar	,,		88
8	Teakwood pannelled door with complete fittings as per existing ones.	S.ft.		120
9	Teakwood windows with iron bars inside glazed and outside panelled shutters, complete.	,,		240
10	Removing and refixing windows	each		4
11	Do doors	,,		1
12	Burnt stone slabs roughly dressed and fixed ...	S.ft.		729
13	Reinforced concrete ventilation	,,		132
14	Steel girders including hoisting and fixing ..	Cwts.		115½
15	Jack arch terracing complete	Sqr.		15·04
16	Cornice 9"×9", complete	R ft.		196
17	Plain parapet wall 2' high	,,		196
18	Plastering with mortar	Sqr.		64·77
19	Flooring with First Class Mangalore tiles on 3" concrete and cement pointing.	,,		13·44
20	Teakwood semi-circular glazed fan light ...	S.ft.		25
21	Teakwood ornamental sun shade	,,		708
22	Silicate painting	Sqr.		16·00
23	White washing	,,		85·13

N. G. KRISHNAIENGAR,
Executive Engineer.